EVIDENCE REVIEW · MAGNETIC EXCURSIONS AND TODAY'S FIELD

When Earth's magnetic field falters

Every so often the geomagnetic field weakens sharply and its direction swings far from its usual axis, typically for a few centuries to several thousand years, before returning to its original polarity. These events are called excursions [1 p. 1][2 p. 1]. Here is what lava, sediments, cave formations and polar ice record about them, how today's field compares, and how recent solar storms rank. Popular "disaster cycle" accounts say excursions come every 6,000 years and that today's field is collapsing; the record supports neither.

By Fact-Checked Science · Published October 13, 2026

OUR ANALYSIS marks our own reasoning and calculations, and the verdicts are our assessment. Everything else comes from the numbered sources.

Real excursions, irregular timing, a modest decline today

OUR ASSESSMENT

12–17
excursions listed in recent reviews since the last full reversal, about 773,000 years ago; about 7 of them adequately or consistently recorded [3][4]

About 9%
how much weaker Earth's axial dipole, the main part of the field, is than in 1840: about 5% per century [5 p. 1][6]

2–5%
of today's strength, roughly: where the dipole bottomed out during the Laschamp excursion, about 41,000 years ago, in recent global field models [7 §3][8 §4.2][2 p. 7]

THE CLAIMS ABOUT EXCURSIONS AND TODAY'S FIELD

FALSE

"This is happening approximately every 6,000 years."

The Disaster Cycle video, 28:45 (our check) [V]

The record keeps no such rhythm. In the last 120,000 years the gaps between dated excursions run from about 5,000 to about 30,000 years, and a 2023 review counts only Laschamp and Blake from that period as reliably established [9 p. 45]. Mono Lake follows Laschamp by about 6,600 years, but Laschamp follows the Norwegian–Greenland Sea event by about 23,400 [10][11]. The six youngest candidates are unusually evenly spaced, about 6,800 years apart, but four of them are disputed, and our cycle test finds that a 6,000-year cycle doesn't fit the dates. See section 2.

FALSE

"The last one to officially be recognized is the one 6,000 years ago... There was a very strong confirmation that came out about a year and a half ago out of the Tiani region in China."

The Disaster Cycle video, 28:58–29:23; the transcript's "Tiani" is probably Tianchi [V]

No inventory of accepted excursions includes one 6,000 years ago; reviews put the youngest well-documented excursion at Mono Lake, about 34,000 years ago [12 p. 1][3]. The Tianchi lava was re-dated to 7,000 ± 900 years in a study published in December 2022, about three years before the video; its authors call it a "heretofore unrecognized" excursion that may have been local, or too brief for other records to catch [13 pp. 1, 5]. A 2025 study did find a weak field in pottery from southern China about 6,100 years ago, but its authors read it as a regional weak spot, not an excursion [14]. The dipole did dip in the mid-Holocene, but only to about 82% of its 1950 strength. See section 3.

FALSE

"We're now down to 15% total field loss according to the ESA Swarm mission. And the mission manager for Swarm came out and said, 'We've gone from losing 5% per century to 5% every decade.'"

The Disaster Cycle video, 38:44 (our check) [V]


Swarm launched in November 2013, too late to measure anything in 2010 [15]. ESA puts the loss at about 9% over 200 years [16], and over Swarm's first decade the dipole weakened by less than half a percent (our calculation from IGRF-14 [17]). The "5% per decade" comes from a 2014 news story, in the reporter's words, not the mission manager's, though the story does paraphrase him on a possible coming flip [18]. See section 4.

1 · THE LONG VIEW

Nearly 800,000 years without a full reversal

The field has kept its present polarity since the Matuyama–Brunhes reversal about 773,000 years ago [4]. Excursions are brief breaks in that long stretch: the field weakens sharply and its direction swings far from the usual axis, typically for a few centuries to several thousand years, then returns to its original polarity instead of settling into a reversed one [1 p. 1][2 p. 1].

The present polarity, with selected excursions



Gaps mark selected excursions and are widened so they show; their width doesn't show how long each lasted. They are the seven a 2007 review judged adequately dated (Mono Lake, Laschamp, Blake, Iceland Basin, Pringle Falls, Big Lost and Stage 17) and three more from section 2 [1 p. 2][19]. Reviews list 12 to 17 excursions since the reversal, about 7 of them adequately or consistently recorded; several between 530,000 and 730,000 years ago are not shown [3][19].

Where excursions are recorded

In lava flows, which lock in the field's direction as they cool [20][19]; in lake and seafloor sediments [23 p. 12][25]; in cave formations dated by uranium and thorium [11][26]; and indirectly in polar ice, where a weak field lets more cosmic rays through to make chlorine-36 and beryllium-10 [1 p. 3][27].

How long they last

From about 300 years to 10,000 [1 p. 2]. Laschamp's main phase lasted about 700 years, within a longest possible span of about 2,550 [11 p. 141]; Blake lasted 4,500 to 6,500 years [26][28 §7].

Not a reversal


In an excursion "the poles may or may not change polarity. However, they always recover to the original polarity in contrast to the reversals" [2 p. 1]. Some records show fully reversed directions for centuries, one for more than about 3,000 years, without a full reversal following [11 p. 141][28 §8.2].

2 · THE LAST 120,000 YEARS

Two excursions are well established worldwide, and the spacing is irregular

Each bar spans an event's best-supported age range, and the rows sort the events by how firmly the evidence establishes them as worldwide excursions. Of the excursions reported in the 1960s and 1970s, a 2007 review says only Blake and Laschamp "have stood the test of time" [29 p. 376].

The last 120,000 years, by strength of evidence



Bar width shows the best-supported age range; the shortest spans are drawn at a minimum width. Lake Mungo, Gothenburg and Hilina Pali are placed by our calibration of their radiocarbon ages [30][31]. All ages are calendar years before present, counted back from 1950. The rows are our reading of the evidence, not a published classification (see the box below).

The spacing is irregular. Mono Lake follows Laschamp by about 6,600 years, Laschamp follows the Norwegian–Greenland Sea event by about 23,400, and that event follows Skálamælifell by about 29,500.

OUR ANALYSIS

How we sorted the rows

The rows are our reading of the evidence. A 2007 review counted Mono Lake among the five best-documented excursions [29 p. 378]; newer global field models find Mono Lake and the Norwegian–Greenland Sea event regional, with only "a moderate dipole moment decrease" [2 p. 1][8 p. 1]. The scientists who dated Post-Blake in lavas consider it global [19]. Iceland Basin, Pringle Falls and the older excursions on the band in section 1 fall outside this chart.

OUR ANALYSIS

Is there a rhythm?

We tested the dated excursions on this chart, except Lake Mungo, whose calendar age is too uncertain, plus Iceland Basin and Pringle Falls, against the proposed 6,000-year cycle and against every cycle length from 3,000 to 60,000 years (Hilina Pali at its best-dated record's 19,500 years). A 6,000-year cycle counted from today doesn't fit them, and no other length stands out from chance. The six youngest of them are unusually evenly spaced, about 6,800 years apart, but four of the six are disputed, adding Lake Mungo breaks the evenness, and the older excursions are dated too loosely to show whether it continues. The full test is on its own page: Is there a 6,000/12,000-year cycle?

3 · RECORD BY RECORD

What each record shows

Each excursion rests on a different mix of lava, sediment, cave and ice records, and on dates of very different quality.

WELL ESTABLISHED · ABOUT 41,100 YEARS AGO

Laschamp

The best-documented excursion: "the most studied geomagnetic event of its kind" [11 p. 139], with the lowest dipole moment of the period 15,000–70,000 years ago, and seen worldwide [2 p. 1]. Fully reversed directions lasted about 250–450 years in Black Sea sediments, depending on the record and its age model [42][10 p. 16][43 suppl.], and a few centuries in several other sediment records [11 p. 141]; one of those, at the Blake–Bahama Outer Ridge, reached only a partly reversed state [44]. Global field models disagree on whether the dipole itself reversed: one finds it fell almost to zero without reversing [8 p. 1], another that it changed sign for about 300 years [2 p. 13]. A dated cave formation in Missouri puts the main phase at 41,100 ± 350 years ago [11 p. 139].

WELL ESTABLISHED · ABOUT 120,000–108,000 YEARS AGO

Blake

A uranium-dated stalagmite from Cobre Cave, Spain, records two reversed intervals between 116,500 ± 700 and 112,000 ± 1,900 years ago [26][19]. A stalagmite from southwest China, reported in 2026, spans about 119,100–108,800 years ago [32]. Some sediment records place it several thousand years earlier: 128,500–122,000 years ago off the US east coast, where it lasted about 6,500 years [28 §7][26]. It is "commonly accepted as a global geomagnetic feature," though still "one of the most ambiguous" of the recent excursions [28 §2].

REAL, BUT WEAKER OR REGIONAL · ABOUT 34,500 YEARS AGO

Mono Lake

Dated to about 34,500 years ago in Black Sea and Drake Passage sediments [10][34]. Greenland ice cores record a peak in cosmogenic isotopes at about this time, seen in chlorine-36 and in beryllium-10, a sign of a weak field worldwide [27][45][8 p. 18]. The dipole weakened far less than at Laschamp [8 p. 9][10], and global models suggest a series of regional excursions between 36,000 and 30,000 years ago [8 p. 1]. The excursion first described at Mono Lake, California, has been related to the Laschamp [46][47]; a 2026 conference report finds a smaller anomaly there about 33,000 years ago, so the type site's dating is still argued over [48][49].

REAL, BUT WEAKER OR REGIONAL · ABOUT 64,500 YEARS AGO

Norwegian–Greenland Sea

A deep intensity low appears in Black Sea cores, though the field's direction there stayed "within the range of normal secular variations" [10]. The excursional directions come from Norwegian–Greenland Sea and Arctic Ocean sediments [2 p. 2][50], which are hard to date and can record false reversals [51 p. 379][28 §2]. A 2021 global model puts the dipole low at 1.87×10^{22} A m^2, roughly a quarter of today's, with excursional directions only regionally [2 pp. 1, 7].

REAL, BUT WEAKER OR REGIONAL · ABOUT 105,000–91,000 YEARS AGO

Post-Blake and Skálamælifell

Lavas in Italy and New Mexico date Post-Blake to about 105,000 years ago, and lavas in Iceland date Skálamælifell to about 94,000; their dates see one interval when "the magnetic field remained unstable between 105 and 94 ka" [19][33]. A Chinese stalagmite separates two phases, at 103,100–99,800 and 94,500–91,000 years ago [32].

SINGLE SITE · ABOUT 36,000–31,000 YEARS AGO

Lake Mungo

Baked earth and clay cooking stones from Aboriginal fireplaces at Lake Mungo, Australia, record the field swinging more than 120° from its present direction [35 p. 243][52][53]. The fireplaces' radiocarbon ages, about 27,500–30,800 years, calibrate to about 31,000–36,000 years ago (OUR ANALYSIS) [35 pp. 246–247][31]; thermoluminescence dating of the same fireplaces gave 33,500 ± 4,300 years [54 p. 194]. That overlaps Mono Lake, but during the main swing the fireplaces record a field about three times today's strength rather than a weak one (a second swing was weak, about a third of today's) [55][54 p. 193], and excursion records more than 45° apart around the globe shouldn't be matched [56], so whether they are the same event is unclear.

SINGLE RECORD · ABOUT 26,500 YEARS AGO

Rockall

An apparent excursion about 26,500 years ago, lasting about 350 years, found so far in a single sediment core from the Rockall Trough in the northeast Atlantic [36 pp. 1823, 1827]. Its discoverers call it "another potential excursion" in a "confusing picture" of possible excursions after Laschamp [36 p. 1837].

DISPUTED · ABOUT 22,000–19,000 YEARS AGO

Hilina Pali

First seen in Hawaiian lavas about 18,000 radiocarbon years old, as a weak field with an unusually shallow inclination [38][57 p. 94]; calibrated, about 21,000–22,000 years ago (OUR ANALYSIS) [30]. Since found in the sediments of Lake Chala in East Africa and of two lakes in the Polar Urals of Arctic Russia [37][12]. In the best-dated record, from Arctic Russia, the pole stayed above about 55°N, so there it looks like extreme secular variation rather than a true excursion [12 §6]; a Black Sea record is similar [58]. At Lake Chala, though, directions briefly reversed, and the Russian study's authors conclude that Hilina Pali was a worldwide weakening of the dipole [12 pp. 17, 19].

DISPUTED · ABOUT 14,500 YEARS AGO AT ITS TYPE SECTION

Gothenburg

First reported in 1971 from a sediment core in Gothenburg, Sweden [59]. In 1976 a study of Swedish late-glacial sediments found no reversal or excursion and called the earlier result an example of the "reinforcement syndrome" [60]; its discoverer defended it [39]. The type section's "flip" is dated to 12,400–12,350 radiocarbon years, about 14,500 calendar years (OUR ANALYSIS) [39][30]. Records from eastern China, the Barents Sea and the Black Sea have since claimed it, the Chinese one about 13,100–12,500 years ago [40][61][62]. It is not among the excursions accepted in international reviews, and a 2023 review calls the question unresolved [3][9 pp. 40–41].

DISPUTED, POSSIBLY LOCAL · ABOUT 7,000 YEARS AGO

Tianchi

Recorded in a lava flow from Changbaishan (Tianchi) volcano on the China–North Korea border [13]. First linked to an excursion about 123,000 years ago, the lava was dated in 2014 to about 17,000 years [63][13 p. 5], then re-dated in 2022 to 7,000 ± 900 years [13 p. 4]. No matching excursion directions have been found elsewhere, so its daters suggest it may have been local, or too brief for other records to catch [13 p. 5].

FOR REFERENCE · 73,900 YEARS AGO

Toba

A supereruption in Sumatra 73,880 ± 320 years ago, not a magnetic event [41]. Two archaeological sites in South Africa and one in Ethiopia show people living through it [64][65].

No excursion 6,000 years ago

What the inventories list

A 2012 conference summary lists the Mono Lake and Laschamp excursions as well documented and notes candidates at 17,000 and 25,000 years ago, and nothing younger [3]. A 2025 study, citing a 2020 review, says the youngest is "the one first discovered at Mono Lake, which occurred about 34 ka ago" [12 p. 1]. In the international lists collected by a 2023 review, the youngest candidate is Tianchi; an excursion at 6,000 years, "Solovki," appears only in work by Russian authors, in a 2004 compilation that also lists one at 2,800 years, "Etrusia"; the review counts neither as reliably established [9 pp. 40, 45].

OUR ANALYSIS

A shallow dip, not an excursion


Two global field models of the last 10,000 years show the dipole sagging to about 82% of each model's 1950 strength at the lowest, and below 90% between about 8,250 and 6,250 years ago, then recovering by 6,000 years ago [66][67]. The study that re-dated Tianchi puts the Holocene's weakest field around 7,000 years ago, about 20% below today's [13 p. 5]. Excursions and reversals happen below about 4×10^{22} A m^2, roughly half today's dipole [68]; the mid-Holocene low stayed well above that. The Tianchi lava, re-dated in a study published in December 2022, is 7,000 ± 900 years old, and no other record matches it [13 pp. 4–5].

4 · THE FIELD TODAY

About 9% weaker since 1840, and far from Laschamp's low

Earth's axial dipole, the main part of the field, is about 9% weaker than it was in 1840 [5 p. 1], a loss of about 5% per century on average [6][69], though the pace varies: around 1980 it was twice as fast as in the 2010s [5 p. 2]. At Laschamp's low the dipole fell to about 5% of today's strength [8 §4.2][7 §3].

Strength of Earth's dipole compared with today



The 1840 bar follows from the roughly 9% decline since then [5 p. 1]. Laschamp's low is the dipole in the LSMOD.2 global field model, built from sediment and lava records: 0.37–0.39 × 10^{22} A m^2, against 7.7 × 10^{22} today [8 §4.2][7 §3][70]; other recent models go lower, to about 2% of today's [8 §4.2][2 p. 7]. A single Black Sea record shows about 6% of today's dipole during the switch into reversed polarity, and an average of about 28% in the short reversed interval [43 p. 811, suppl.][42]. At the surface the field was weak everywhere, below 1 μT in places, against about 22–67 μT today [8 §4.6] (OUR ANALYSIS) [17].

About 9%

weaker than in 1840 [5 p. 1]. ESA puts the loss at about 9% over 200 years [16]. The change is uneven: since 2014 the field has weakened over Canada and the South Atlantic and strengthened over Siberia [15][71].

About 2,500 km

OUR ANALYSIS

how far the north magnetic pole now lies from where James Clark Ross located it in 1831, about 2,900 km along its winding path, by our calculation from NOAA's yearly positions [72]. It sped up from at most about 15 km a year before 1990 to 50–60 km a year in the early 2000s, then slowed to about 35 km a year, which the British Geological Survey calls the biggest deceleration it has seen [73][74][75 p. 12][76 §1.6].

0.9%

of Earth's surface: how much the South Atlantic Anomaly, where the field is weakest (below 26,000 nT), has grown since 2014, an area nearly half the size of continental Europe. Satellites passing over it receive higher radiation doses, which can damage their hardware [15][71].

In a Swarm scientist's words

Nils Olsen of the Technical University of Denmark, a member of ESA's Swarm team, to NASA in 2014

> *"The magnetic field changes in a chaotic manner, and we do not know why it changes in the way it does nor how it will evolve in the future."*
>
> NASA Earth Observatory (2014) [77]

> *"There is no periodic behavior, and it is therefore rather difficult, if not impossible, to predict how the magnetic field evolves over time."*
>
> NASA Earth Observatory (2014) [77]

"15% gone, ten times faster"?

The video's timeline, against the record


THE VIDEO SAYS (38:04–39:01)	WHAT THE RECORD SHOWS
By 2000 the north magnetic pole "was moving at 20 kilometers a year."	About 22 km a year in the early 1990s, but nearly 50 km a year by 2000 (OUR ANALYSIS) [72]; it accelerated between 1990 and 2005 [73].
"We had lost 10% of Earth's magnetic field in only about 150 years."	About 8% from 1840 to 2000 (OUR ANALYSIS) [5 p. 2][17]; about 5% per century [6].
In 2006, "we go from 5% loss per century to 5% per decade."	The dipole lost about half a percent per decade between 2000 and 2020 (OUR ANALYSIS) [17], slower than around 1980 [5 p. 2].
The pole was then "racing at about 40 kilometers a year."	It moved 54–55 km a year in 2005–2007 [72], after accelerating between 1990 and 2005 [73].
By 2010, "15% total field loss according to the ESA Swarm mission."	Swarm launched on November 22, 2013 [15], with first results in June 2014 [78]. ESA's figure is about 9% over 200 years [16].
The Swarm mission manager said, "We've gone from losing 5% per century to 5% every decade."	ESA's 2014 release quotes the mission manager, Rune Floberghagen, only on the satellites' performance [78]. A *Live Science* story paraphrases him as saying the poles may be getting ready to flip and the field is weakening faster, but its "5 percent per decade, or 10 times faster than thought" is the reporter's narration, not a quotation [18]. NASA's write-up of the same results says about 5% over the past century [77].

Over Swarm's first decade, 2014–2024, the dipole moment weakened by about 0.5%, the axial dipole by about 0.3% and the average field at the surface by about 0.3% (OUR ANALYSIS) [17]. Pole speeds are great-circle distances between NOAA's yearly positions [72].

5 · SIX LANDMARK STORMS SINCE 1859

May 2024's storm was the strongest in two decades, and about half the size of 1859's

Storm strength is measured by the Dst index: the average magnetic disturbance at four low-latitude observatories, Hermanus, Kakioka, Honolulu and San Juan, scaled to the magnetic equator. It runs negative, in nanotesla (nT), and its record starts in 1957 [79 §2][80]. Earlier storms are reconstructed from historical records.



1859: Telegraph systems were disrupted worldwide [81]. Aurora was seen across the Caribbean and Mexico, in Chile, and in Wakayama in southern Japan [82 §3.3][83 §3.1].

1921: Fires destroyed the railroad station at Brewster, New York, after flames broke out at its telegraph switchboard, and hit the telegraph station at Karlstad, Sweden [84 p. 525][85 p. 3][86 p. 356]; a signal-tower fire in New York City, often blamed on the storm, may have been unrelated [87][85 p. 2]. Aurora was reported from Apia, Samoa [84].

1989: The Hydro-Québec grid collapsed in about 90 seconds, and about 6 million people lost power for about nine hours [88][89]. The blackout struck early in the storm, about 17–18 hours before the Dst low [90][80].

2003 (October): Storms on October 29–31 caused an outage of under an hour in Malmö, Sweden, affecting about 50,000 customers [91 p. 1782][92], and damage that led several large transformers in South Africa to fail in the following months [93][94]. The weeks of solar outbursts around them also brought satellite faults and polar flight reroutes [95 pp. 1, 18].

2003 (November 20): It came from an eruption on November 18 in a sunspot region returning after the Halloween outbursts, and was the strongest storm of that solar cycle [96 §1][97 §1.1].

2024: The first G5, or extreme, storm since 2003 [98][99]. Aurora reached the southern tips of Africa and South America and was seen across much of the United States and in Mexico [100][101 §7][99].

Minimum hourly Dst. 1859: Cliver and Dietrich's working estimate, with the range of empirical hourly estimates; newer estimates run from about −870 to −980 nT [102 §2.2.1][103][104 §4]. 1921: the published ± [105]. 1989 and 2003: final values; 2024: provisional, −412 nT in the real-time data [80][106][101].

The Colaba reading

A single 1859 reading at Colaba, in Bombay, India, showed the field dropping by about 1,600 nT [107][102 §2.2.1]; the often-quoted −1,760 nT is a storm size estimated from how fast the solar eruption reached Earth, which its authors judged consistent with the Colaba dip; it is not a reading [107][102 §2.2.1]. Most studies think auroral or other local currents added to that dip, and some suspect a recording problem, so the hourly estimates are shown [104 §1][108][103]. Its first interpreters still argue for the ring current, the source Dst measures [109].

How May 2024 ranks

By Dst, the May 2024 storm ranks sixth since 1957, behind March 1989 (−589 nT), July 1959 (−429), September 1957 (−427), February 1958 (−426) and November 2003 (−422) [80][101 §9]. The 1859 and 1921 storms, reconstructed from historical records, were about twice as strong [102 §2.2.1][105].

6 · LIMITS

What this page can and can't settle

The rows are a judgment

No published classification sorts excursions into our three rows. They follow reviews and global models [29 pp. 376, 378][2 p. 1][8 p. 1], and a reader could defend moving Mono Lake up or the Norwegian–Greenland Sea event down.

Ages carry real uncertainty

Lake Mungo, Gothenburg and the Hawaiian Hilina Pali lavas rest on radiocarbon ages from the 1960s and 1970s, which we calibrated [30][31]. If Gothenburg's dates came from marine shells, a reservoir correction would make it about 13,800 years old (OUR ANALYSIS).

Some sources read in part

Several papers were behind paywalls, so we used their abstracts, later papers that quote them, or the authors' own conference abstracts; the verification log lists each. None of the verdicts rests on those alone.

What would change these verdicts

01 — Excursions found at regular intervals in well-dated records from several regions, rather than in a short recent run of disputed events.

02 — A well-dated excursion about 6,000 years ago in several independent records, or new evidence that Tianchi's was worldwide.

03 — Measurements showing the dipole weakening several times faster than its roughly 5% per century since 1840.

Related checks

FALSE Every 6,000 years? The Disaster Cycle, Fact-Checked
FALSE 15% gone, ten times faster? The Disaster Cycle, Fact-Checked
FALSE More auroras from less solar input? The Disaster Cycle, Fact-Checked
FALSE The 2025 model already failing? The Disaster Cycle, Fact-Checked
FALSE 55% of the field gone? The Disaster Cycle, Fact-Checked

Sources

Bracketed numbers refer to this list; p. and pp. give pages (the journal's own page numbers), § gives a section, and Abstract, Fig., Table and suppl. (supplementary materials) name the part of a work we used. [V] is the video we checked. Links checked October 13, 2026.

1 Roberts, A. P. (2008). Geomagnetic excursions: Knowns and unknowns. *Geophysical Research Letters* 35(17), L17307.

2 Panovska, S., Korte, M., Liu, J., and Nowaczyk, N. (2021). Global evolution and dynamics of the geomagnetic field in the 15–70 kyr period based on selected paleomagnetic sediment records. *Journal of Geophysical Research: Solid Earth* 126(12), e2021JB022681. CC BY 4.0.

3 Channell, J. E. T. (2012). Geomagnetic excursions in the Brunhes and Matuyama Chrons: Do they come in bunches? *Geophysical Research Abstracts* 14, EGU2012-10478 (conference abstract).

4 Singer, B. S., Jicha, B. R., Mochizuki, N., and Coe, R. S. (2019). Synchronizing volcanic, sedimentary, and ice core records of Earth's last magnetic polarity reversal. *Science Advances* 5(8), eaaw4621. CC BY-NC 4.0.

5 Finlay, C. C., Aubert, J., and Gillet, N. (2016). Gyre-driven decay of the Earth's magnetic dipole. *Nature Communications* 7, 10422. CC BY 4.0.

6 Gubbins, D., Jones, A. L., and Finlay, C. C. (2006). Fall in Earth's magnetic field is erratic. *Science* 312(5775), 900–902.

7 Larsen, N., Usoskin, I., Mishev, A., Kolodobskiy, S., and Väisänen, P. (2026). Reduced geomagnetic shielding during the Laschamps excursion and its impact on cosmic-ray-induced atmospheric radiation. *Journal of Geophysical Research: Space Physics* 131(2), e2025JA034820. CC BY 4.0.

8 Korte, M., Brown, M. C., Panovska, S., and Wardinski, I. (2019). Robust characteristics of the Laschamp and Mono Lake geomagnetic excursions: results from global field models. *Frontiers in Earth Science* 7, 86. CC BY 4.0.

9 Bakhmutov, V., Melnyk, H., Hlavatskyi, D., and Poliachenko, I. (2023). Geomagnetic field excursions of the Brunhes chron. Part 1: A historical overview and current state of research. *Visnyk of Taras Shevchenko National University of Kyiv. Geology* 4(103), 38–48 (in Ukrainian).

10 Liu, J., Nowaczyk, N. R., Panovska, S., Korte, M., and Arz, H. W. (2020). The Norwegian-Greenland Sea, the Laschamps, and the Mono Lake excursions recorded in a Black Sea sedimentary sequence spanning from 68.9 to 14.5 ka. *Journal of Geophysical Research: Solid Earth* 125(8), e2019JB019225. CC BY-NC 4.0.

11 Lascu, I., Feinberg, J. M., Dorale, J. A., Cheng, H., and Edwards, R. L. (2016). Age of the Laschamp excursion determined by U-Th dating of a speleothem geomagnetic record from North America. *Geology* 44(2), 139–142.

12 Scheidt, S., Ólafsdóttir, S., Brendryen, J., et al. (2025). New insights into the proposed geomagnetic excursion Hilina Pali from high-resolution lake sediment cores from the Polar Ural Mountains, Arctic Russia. *Journal of Geophysical Research: Solid Earth* 130(11), e2025JB032561. CC BY 4.0.

13 Pan, B., de Silva, S. L., Danišík, M., Schmitt, A. K., and Miggins, D. P. (2022). The Qixiangzhan eruption, Changbaishan-Tianchi volcano, China/DPRK: new age constraints and their implications. *Scientific Reports* 12, 22485. CC BY 4.0.

14 Luo, X., Liu, J., Wang, H., et al. (2025). Low geomagnetic field intensity in southern China 6,000 years ago. *Geophysical Research Letters* 52(9), e2024GL113552. CC BY 4.0.

15 European Space Agency (2025, October 13). Swarm reveals growing weak spot in Earth's magnetic field. News release.

16 European Space Agency (2020, May 20). Swarm probes weakening of Earth's magnetic field. News release.

17 IAGA Working Group V-MOD (2024). International Geomagnetic Reference Field, 14th generation (IGRF-14): coefficients 1900–2025 and secular variation 2025–2030. Data file, NOAA National Centers for Environmental Information.

18 Dickerson, K. (2014, July 8). Earth's magnetic field is weakening 10 times faster now. *Live Science*.

19 Singer, B. S., Guillou, H., Jicha, B. R., Zanella, E., and Camps, P. (2014). Refining the Quaternary Geomagnetic Instability Time Scale (GITS): Lava flow recordings of the Blake and Post-Blake excursions. *Quaternary Geochronology* 21, 16–28.

20 Champion, D. E., Lanphere, M. A., and Kuntz, M. A. (1988). Evidence for a new geomagnetic reversal from lava flows in Idaho: Discussion of short polarity reversals in the Brunhes and late Matuyama polarity chrons. *Journal of Geophysical Research: Solid Earth* 93(B10), 11667–11680.

21 Singer, B. S., Relle, M. K., Hoffman, K. A., et al. (2002). $^{40}Ar/^{39}Ar$ ages from transitionally magnetized lavas on La Palma, Canary Islands, and the geomagnetic instability timescale. *Journal of Geophysical Research: Solid Earth* 107(B11), 2307.

22 Singer, B. S., Jicha, B. R., Kirby, B. T., Geissman, J. W., and Herrero-Bervera, E. (2008). $^{40}Ar/^{39}Ar$ dating links Albuquerque Volcanoes to the Pringle Falls excursion and the Geomagnetic Instability Time Scale. *Earth and Planetary Science Letters* 267(3–4), 584–595.

23 Channell, J. E. T., Hodell, D. A., and Curtis, J. H. (2012). ODP Site 1063 (Bermuda Rise) revisited: Oxygen isotopes, excursions and paleointensity in the Brunhes Chron. *Geochemistry, Geophysics, Geosystems* 13(2), Q02001.

24 Herrero-Bervera, E., Helsley, C. E., Sarna-Wojcicki, A. M., et al. (1994). Age and correlation of a paleomagnetic episode in the western United States by $^{40}Ar/^{39}Ar$ dating and tephrochronology: The Jamaica, Blake, or a new polarity episode? *Journal of Geophysical Research: Solid Earth* 99(B12), 24091–24103.

25 Channell, J. E. T., Vázquez Riveiros, N., Gottschalk, J., Waelbroeck, C., and Skinner, L. C. (2017). Age and duration of Laschamp and Iceland Basin geomagnetic excursions in the South Atlantic Ocean. *Quaternary Science Reviews* 167, 1–13.

26 Osete, M.-L., Martín-Chivelet, J., Rossi, C., et al. (2012). The Blake geomagnetic excursion recorded in a radiometrically dated speleothem. *Earth and Planetary Science Letters* 353–354, 173–181.

27 Wagner, G., Beer, J., Laj, C., et al. (2000). Chlorine-36 evidence for the Mono Lake event in the Summit GRIP ice core. *Earth and Planetary Science Letters* 181(1–2), 1–6.

28 Bourne, M., Mac Niocaill, C., Thomas, A. L., Knudsen, M. F., and Henderson, G. M. (2012). Rapid directional changes associated with a 6.5 kyr-long Blake geomagnetic excursion at the Blake–Bahama Outer Ridge. *Earth and Planetary Science Letters* 333–334, 21–34.

29 Laj, C., and Channell, J. E. T. (2007). Geomagnetic excursions. In *Treatise on Geophysics*, vol. 5, *Geomagnetism*, 373–416. Elsevier.

30 Reimer, P. J., Austin, W. E. N., Bard, E., et al. (2020). The IntCal20 Northern Hemisphere radiocarbon age calibration curve (0–55 cal kBP). *Radiocarbon* 62(4), 725–757. CC BY 4.0.

31 Hogg, A. G., Heaton, T. J., Hua, Q., et al. (2020). SHCal20 Southern Hemisphere calibration, 0–55,000 years cal BP. *Radiocarbon* 62(4), 759–778. CC BY 4.0.

32 Shen, Z., Li, Y., Yi, L., et al. (2026). Decadal-scale in situ scanning of a stalagmite from southwest China reveals Blake geomagnetic excursion structure. *Geophysical Research Letters* 53(2), e2025GL117878. CC BY 4.0.

33 Jicha, B. R., Kristjánsson, L., Brown, M. C., et al. (2011). New age for the Skálamælifell excursion and identification of a global geomagnetic event in the late Brunhes chron. *Earth and Planetary Science Letters* 310(3–4), 509–517.

34 Nowaczyk, N. R., Liu, J., Lamy, F., Lembke-Jene, L., and Arz, H. W. (2025). The Mono Lake and Laschamps geomagnetic excursions recorded by sediments in the Drake Passage. *Journal of Geophysical Research: Solid Earth* 130(1), e2024JB029835. CC BY-NC-ND 4.0.

35 Barbetti, M., and Polach, H. (1973). ANU radiocarbon date list V. *Radiocarbon* 15(2), 241–251.

36 Channell, J. E. T., Harrison, R. J., Lascu, I., et al. (2016). Magnetic record of deglaciation using FORC-PCA, sortable-silt grain size, and magnetic excursion at 26 ka, from the Rockall Trough (NE Atlantic). *Geochemistry, Geophysics, Geosystems* 17(5), 1823–1841.

37 Di Chiara, A., Karlouskovski, V., Maher, B. A., et al. (2025). A continuous 150-kyr record of geomagnetic field variations from Lake Chala, eastern equatorial Africa. *Geochemistry, Geophysics, Geosystems* 26(4), e2024GC011933. CC BY 4.0.

38 Coe, R. S., Grommé, S., and Mankinen, E. A. (1978). Geomagnetic paleointensities from radiocarbon-dated lava flows on Hawaii and the question of the Pacific nondipole low. *Journal of Geophysical Research* 83(B4), 1740–1756.

39 Mörner, N.-A. (1977). The Gothenburg magnetic excursion. *Quaternary Research* 7(3), 413–427.

40 Chen, Z., Yuan, F., Zhang, J., et al. (2020). Paleomagnetic evidence for the Gothenburg geomagnetic excursion during the Pleistocene–Holocene transition recorded in the Paleo-Danyang Lake, eastern China. *Journal of Asian Earth Sciences* 201, 104140.

41 Storey, M., Roberts, R. G., and Saidin, M. (2012). Astronomically calibrated $^{40}Ar/^{39}Ar$ age for the Toba supereruption and global synchronization of late Quaternary records. *Proceedings of the National Academy of Sciences* 109(46), 18684–18688.

42 Nowaczyk, N. R., Arz, H. W., Frank, U., Kind, J., and Plessen, B. (2012). Dynamics of the Laschamp geomagnetic excursion from Black Sea sediments. *Earth and Planetary Science Letters* 351–352, 54–69.

43 Cooper, A., Turney, C. S. M., Palmer, J., et al. (2021). A global environmental crisis 42,000 years ago. *Science* 371(6531), 811–818.

44 Bourne, M. D., Mac Niocaill, C., Thomas, A. L., and Henderson, G. M. (2013). High-resolution record of the Laschamp geomagnetic excursion at the Blake-Bahama Outer Ridge. *Geophysical Journal International* 195(3), 1519–1533.

45 Guillou, H., Laj, C., Carracedo, J.-C., et al. (2010). Identification and dating of the Mono Lake excursion in lava flows from the Canary islands. *Geophysical Research Abstracts* 12, EGU2010-3111-1 (conference abstract).

46 Ali, G., Lin, K., Hemming, S., and Wang, X. (2026). Carbonate U/Th ages confirm the Mono Basin excursion as the Laschamps geomagnetic excursion. *Geological Society of America Bulletin* 138(7–8), 2910–2918.

47 Vazquez, J. A., and Lidzbarski, M. I. (2012). High-resolution tephrochronology of the Wilson Creek Formation (Mono Lake, California) and Laschamp event using ^{238}U-^{230}Th SIMS dating of accessory mineral rims. *Earth and Planetary Science Letters* 357–358, 54–67.

48 Jensen, B., Ibarra, D., Reyes, A., et al. (2026). Revisiting the Mono Lake Excursion Type Section with High-Resolution Paleomagnetic Records. EGU General Assembly 2026, EGU26-15660 (conference abstract). CC BY 4.0.

49 Benson, L., Liddicoat, J., Smoot, J., et al. (2003). Age of the Mono Lake excursion and associated tephra. *Quaternary Science Reviews* 22(2–4), 135–140.

50 Nowaczyk, N. R., Frederichs, T. W., Eisenhauer, A., and Gard, G. (1994). Magnetostratigraphic data from late Quaternary sediments from the Yermak Plateau, Arctic Ocean: Evidence for four geomagnetic polarity events within the last 170 ka of the Brunhes Chron. *Geophysical Journal International* 117(2), 453–471.

51 Channell, J. E. T. (2006). Late Brunhes polarity excursions (Mono Lake, Laschamp, Iceland Basin and Pringle Falls) recorded at ODP Site 919 (Irminger Basin). *Earth and Planetary Science Letters* 244(1–2), 378–393.

52 Barbetti, M., and McElhinny, M. (1972). Evidence of a geomagnetic excursion 30,000 yr BP. *Nature* 239(5371), 327–330.

53 Barbetti, M. F., and McElhinny, M. W. (2010). The Lake Mungo geomagnetic excursion (dataset, from their 1976 paper in *Philosophical Transactions of the Royal Society A* 281, 515–542). MagIC database, contribution 18065.

54 Barbetti, M. (1980). Geomagnetic strength over the last 50,000 years and changes in atmospheric ^{14}C concentration: emerging trends. *Radiocarbon* 22(2), 192–199.

55 Huxtable, J., and Aitken, M. J. (1977). Thermoluminescent dating of Lake Mungo geomagnetic polarity excursion. *Nature* 265(5589), 40–41.

56 Merrill, R. T., and McFadden, P. L. (2005). The use of magnetic field excursions in stratigraphy. *Quaternary Research* 63(3), 232–237.

57 Rubin, M., and Berthold, S. M. (1961). U. S. Geological Survey radiocarbon dates VI. *Radiocarbon* 3, 86–98.

58 Liu, J., Nowaczyk, N. R., Frank, U., and Arz, H. W. (2018). A 20–15 ka high-resolution paleomagnetic secular variation record from Black Sea sediments – no evidence for the 'Hilina Pali excursion'? *Earth and Planetary Science Letters* 492, 174–185.

59 Mörner, N.-A., Lanser, J. P., and Hospers, J. (1971). Late Weichselian palaeomagnetic reversal. *Nature Physical Science* 234(52), 173–174.

60 Thompson, R., and Berglund, B. (1976). Late Weichselian geomagnetic 'reversal' as a possible example of the reinforcement syndrome. *Nature* 263(5577), 490–491.

61 Guskova, E. G., Raspopov, O. M., Piskarev, A. L., et al. (2007). Manifestation of the Gothenburg geomagnetic field excursion in the Barents Sea bottom sediments. *Geomagnetism and Aeronomy* 47(6), 781–786.

62 Demidenko, E. L., Faustov, S. S., and Nikolaev, S. D. (1998). Gothenburg magnetic excursion in sediments of the Black Sea. *Stratigraphy and Geological Correlation* 6(2), 81–90 (in Russian; abstract read in the record of a related dataset, PANGAEA 778851).

63 Singer, B. S., Jicha, B. R., He, H., and Zhu, R. (2014). Geomagnetic field excursion recorded 17 ka at Tianchi Volcano, China: New $^{40}Ar/^{39}Ar$ age and significance. *Geophysical Research Letters* 41(8), 2794–2802.

64 Smith, E. I., Jacobs, Z., Johnsen, R., et al. (2018). Humans thrived in South Africa through the Toba eruption about 74,000 years ago. *Nature* 555(7697), 511–515.

65 Kappelman, J., Todd, L. C., Davis, C. A., et al. (2024). Adaptive foraging behaviours in the Horn of Africa during Toba supereruption. *Nature* 628(8007), 365–372.

66 Korte, M. (2016). CALS10k.2 and HFM.OL1.A1 geomagnetic field models and fortran code for evaluation. EarthRef Digital Archive 2207 (the model files of Constable, Korte and Panovska 2016).

67 Constable, C., Korte, M., and Panovska, S. (2016). Persistent high paleosecular variation activity in southern hemisphere for at least 10 000 years. *Earth and Planetary Science Letters* 453, 78–86. CC BY-NC-ND 4.0.

68 Knudsen, M. F., Riisager, P., Donadini, F., et al. (2008). Variations in the geomagnetic dipole moment during the Holocene and the past 50 kyr. *Earth and Planetary Science Letters* 272(1–2), 319–329.

69 Brown, M., Korte, M., Holme, R., Wardinski, I., and Gunnarson, S. (2018). Earth's magnetic field is probably not reversing. *Proceedings of the National Academy of Sciences* 115(20), 5111–5116.

70 Korte, M., and Brown, M. (2019). LSMOD.2 – Global paleomagnetic field model for 50–30 ka BP. GFZ Data Services (dataset). CC BY 4.0.

71 Finlay, C. C., Kloss, C., and Gillet, N. (2025). Core field changes from eleven years of Swarm satellite observations. *Physics of the Earth and Planetary Interiors* 368, 107447. CC BY 4.0.

72 NOAA National Centers for Environmental Information. Wandering of the geomagnetic poles, with its yearly north dip pole positions, 1590–2025 (NP.xy). Accessed October 13, 2026.

73 Livermore, P. W., Finlay, C. C., and Bayliff, M. (2020). Recent north magnetic pole acceleration towards Siberia caused by flux lobe elongation. *Nature Geoscience* 13(5), 387–391.

74 British Geological Survey (2024, December 17). Airlines, shipping companies and sleigh drivers rush to update crucial navigation systems ahead of Christmas rush. News release.

75 NOAA National Centers for Environmental Information and British Geological Survey (2025). State of the Geomagnetic Field 2025.

76 Chulliat, A., Brown, W., Nair, M., et al. (2025). The US/UK World Magnetic Model for 2025–2030: Technical Report. NOAA National Centers for Environmental Information.

77 NASA Earth Observatory (2014, September 7). Measuring Earth's magnetism. Image of the Day.

78 European Space Agency (2014, June 19). Swarm reveals Earth's changing magnetism. News release.

79 Sugiura, M., and Kamei, T. (1991). Equatorial Dst index 1957–1986. *IAGA Bulletin* 40. Web version: On Dst index, World Data Center for Geomagnetism, Kyoto.

80 Nose, M., Sugiura, M., Kamei, T., Iyemori, T., and Koyama, Y. (2015). Dst index (dataset). World Data Center for Geomagnetism, Kyoto: final and provisional hourly values, read October 13, 2026.

81 Green, J. L., and Boardsen, S. (2006). Duration and extent of the great auroral storm of 1859. *Advances in Space Research* 38(2), 130–135.

82 Hayakawa, H., Ebihara, Y., Hand, D. P., et al. (2018). Low-latitude aurorae during the extreme space weather events in 1859. *The Astrophysical Journal* 869(1), 57.

83 Hayakawa, H., Iwahashi, K., Tamazawa, H., et al. (2016). East Asian observations of low-latitude aurora during the Carrington magnetic storm. *Publications of the Astronomical Society of Japan* 68(6), 99.

84 Silverman, S. M., and Cliver, E. W. (2001). Low-latitude auroras: the magnetic storm of 14–15 May 1921. *Journal of Atmospheric and Solar-Terrestrial Physics* 63(5), 523–535.

85 Love, J. J., Lucas, G. M., Kelbert, A., et al. (2025). The impact of the May 1921 superstorm on American telecommunication systems. *Space Weather* 23(7), e2025SW004563. CC BY 4.0.

86 Kočí, E., and Valach, F. (2023). The record of the magnetic storm on 15 May 1921 in Stará Ďala (present-day Hurbanovo) and its compliance with the global picture of this extreme event. *Annales Geophysicae* 41(2), 355–368. CC BY 4.0.

87 Hapgood, M. (2019). The great storm of May 1921: An exemplar of a dangerous space weather event. *Space Weather* 17(7), 950–975. CC BY 4.0.

88 NOAA National Environmental Satellite, Data, and Information Service (2015, October 19). When solar storms attack: Space weather and our infrastructure.

89 Hydro-Québec. Understanding electricity: March 1989 blackout. Accessed October 13, 2026.

90 Boteler, D. H. (2019). A 21st century view of the March 1989 magnetic storm. *Space Weather* 17(10), 1427–1441.

91 Wik, M., Pirjola, R., Lundstedt, H., et al. (2009). Space weather events in July 1982 and October 2003 and the effects of geomagnetically induced currents on Swedish technical systems. *Annales Geophysicae* 27(4), 1775–1787. CC BY 3.0.

92 Pulkkinen, A., Lindahl, S., Viljanen, A., and Pirjola, R. (2005). Geomagnetic storm of 29–31 October 2003: Geomagnetically induced currents and their relation to problems in the Swedish high-voltage power transmission system. *Space Weather* 3(8), S08C03.

93 Gaunt, C. T. (2014). Reducing uncertainty – responses for electricity utilities to severe solar storms. *Journal of Space Weather and Space Climate* 4, A01.

94 Gaunt, C. T., and Coetzee, G. (2007). Transformer failures in regions incorrectly considered to have low GIC-risk. *2007 IEEE Lausanne Power Tech*, 807–812.

95 National Oceanic and Atmospheric Administration (2004). Service assessment: Intense space weather storms, October 19 – November 07, 2003. US Department of Commerce.

96 Grechnev, V. V., Uralov, A. M., Chertok, I. M., et al. (2014). A challenging solar eruptive event of 18 November 2003 and the causes of the 20 November geomagnetic superstorm. IV. Unusual magnetic cloud and overall scenario. *Solar Physics* 289(12), 4653–4673.

97 Grechnev, V. V., Uralov, A. M., Slemzin, V. A., et al. (2014). A challenging solar eruptive event of 18 November 2003 and the causes of the 20 November geomagnetic superstorm. I. Unusual history of an eruptive filament. *Solar Physics* 289(1), 289–318.

98 NOAA Space Weather Prediction Center (2024, May 10). G5 conditions observed!

99 Johnson-Groh, M. (2024, May 16). How NASA tracked the most intense solar storm in decades. NASA.

100 Karan, D. K., Martinis, C. R., Daniell, R. E., et al. (2024). GOLD observations of the merging of the southern crest of the equatorial ionization anomaly and aurora during the 10 and 11 May 2024 Mother's Day super geomagnetic storm. *Geophysical Research Letters* 51(15), e2024GL110632. CC BY-NC-ND 4.0.

101 Hayakawa, H., Ebihara, Y., Mishev, A., et al. (2025). The solar and geomagnetic storms in 2024 May: A flash data report. *The Astrophysical Journal* 979(1), 49. CC BY 4.0.

102 Cliver, E. W., and Dietrich, W. F. (2013). The 1859 space weather event revisited: limits of extreme activity. *Journal of Space Weather and Space Climate* 3, A31.

103 Love, J. J., Rigler, E. J., Hayakawa, H., and Mursula, K. (2024). On the uncertain intensity estimate of the 1859 Carrington storm. *Journal of Space Weather and Space Climate* 14, 21. CC BY 4.0.

104 Hayakawa, H., Nevanlinna, H., Blake, S. P., et al. (2022). Temporal variations of the three geomagnetic field components at Colaba Observatory around the Carrington storm in 1859. *The Astrophysical Journal* 928(1), 32. CC BY 4.0.

105 Love, J. J., Hayakawa, H., and Cliver, E. W. (2019). Intensity and impact of the New York Railroad superstorm of May 1921. *Space Weather* 17(8), 1281–1292. CC BY 4.0.

106 NOAA Space Weather Prediction Center (2024, May 22). Historical comparison of May 2024 solar storms.

107 Tsurutani, B. T., Gonzalez, W. D., Lakhina, G. S., and Alex, S. (2003). The extreme magnetic storm of 1–2 September 1859. *Journal of Geophysical Research: Space Physics* 108(A7), 1268.

108 Love, J. J., and Mursula, K. (2024). Challenging ring-current models of the Carrington storm. *Journal of Geophysical Research: Space Physics* 129(9), e2024JA032541. CC BY 4.0.

109 Tsurutani, B. T., Lakhina, G. S., and Hajra, R. (2023). Comments on "New insights from the 2003 Halloween storm into the Colaba 1600 nT magnetic depression during the 1859 Carrington storm" by S. Ohtani (2022). *Journal of Geophysical Research: Space Physics* 128(6), e2022JA031034.

V SpaceWeatherNews (S0) (2026). THE DISASTER CYCLE – The Evidence. YouTube video, quoted from the transcript behind our check of the video.

METHOD

How this was checked

On October 13, 2026, we checked every statement, number and chart mark of the original infographic against primary sources, about 130 items in all, in four parallel passes: the long record and the older excursions, the younger and disputed excursions, today's field, and the storms. We resolved every DOI and read the open papers in full. Where a paper was closed, we used its abstract, later papers that quote it, or its authors' conference abstracts, and the locator says which part we used. We also read the hourly Dst values for every storm on the page from Kyoto's data service [80].

The check changed the infographic in several places. Gothenburg's type section is about 14,500 years old once its radiocarbon age is calibrated; the 12,500–13,000 it showed belongs to a later record [39][40]. Lake Mungo, drawn at its radiocarbon age, moves to about 36,000–31,000 years ago, and Tianchi is 7,000 ± 900 years old [13 p. 4]. Post-Blake and Skálamælifell are drawn as two phases [32]. The north magnetic pole now lies about 2,500 km from where it was found in 1831, not 2,200, and the Colaba reading of 1859 was about 1,600 nT; the −1,760 nT is an estimated storm size [107]. Laschamp's 0–6% and 28% come from one Black Sea record; the global dipole low was about 2–5% [8 §4.2][7 §3]. The change log lists the main changes.

After the page was built, a second reviewer who hadn't seen the drafting re-ran every calculation from the raw data, checked about 95 of the references against their sources and read the page for fairness. Every chart mark and calculation reproduced. The changes that followed: the verdict on the 6,000-year rhythm now cites a review that does count only Laschamp and Blake as reliably established in that period [9 p. 45]; the Tianchi verdict keeps the video's time phrase, gives its daters' hedge in full and adds a 2025 study of a weak regional field in China [14]; the Laschamp low is given as 2–5% across recent models; and a dozen smaller wording and locator fixes.

The verdicts and the items tagged "Our analysis" are our own work, built on the cited sources: the radiocarbon calibrations, with IntCal20 and SHCal20 [30][31]; the north magnetic pole's distance and speeds, from NOAA's yearly positions [72]; the decline figures and today's surface field, from IGRF-14 [17]; the Holocene dipole, from two published field models [66]; and the storm ranking, from Kyoto's Dst record. The three evidence rows are our reading of the sources, not a published classification.

The video is quoted from the transcript behind our check of it [V].

This page was researched and written with Claude, an AI assistant made by Anthropic, and then re-checked against its sources in a separate verification pass.

The verdicts on this page

FALSE — The evidence contradicts the claim.

All ten verdicts, and how we check

CORRECTIONS

Corrections and changes

If we get something wrong, we fix it and record the change below with the date. If a correction changes a verdict, the log says what the old verdict was.

Change log

Oct 13, 2026 — Published on factchecked.science after a full check against the sources. The main changes from the infographic: Gothenburg is placed at its Swedish type section, about 14,500 years ago once its radiocarbon age is calibrated, with later claims at 12,500–13,100; Lake Mungo, drawn at its radiocarbon age, moved to about 36,000–31,000 years ago; Tianchi is 7,000 ± 900 years old and possibly local; Hilina Pali is about 22,000–19,000 years ago, and its 55°N limit holds for one record, not all; Post-Blake and Skálamælifell are drawn as two phases; Big Lost is about 560,000–580,000 years old, and the band's gaps are a selection; the Matuyama–Brunhes reversal is about 773,000 years ago. Laschamp's "0–6%" and "below 28%" are a single Black Sea record's values, so the chart now compares the global dipole: about 110% in 1840, 100% today and about 2–5% at Laschamp's low. The pole now lies about 2,500 km from where it was found in 1831, not 2,200. The Colaba reading was about 1,600 nT; the −1,760 nT is an inferred storm size. Sweden's 2003 outage lasted under an hour, South Africa's transformers failed in the following months, and May 2024's storm is drawn at its provisional −406 nT. The scientist quoted is Nils Olsen of the Technical University of Denmark, on ESA's Swarm team, in a 2014 NASA story. Added the claims each part answers, with our verdicts.

Sep 28, 2026 — Original infographic, "When Earth's magnetic field falters," compiled from the scientific literature.

Fact-Checked Science is independent. It isn't affiliated with the channels, presenters or authors whose claims it checks.